



PLAN VIEW



SECTION

STABILIZED CONSTRUCTION ENTRANCE

N.T.S.

Installation Details:

1. Grade entrance by removing sod down to firm subgrade.
2. Place filter cloth over the entrance subgrade. Min. width = 12', Min. length = 50'.
3. Construct aggregate pad with positive drainage a minimum of 6" thick using 2" stone or reclaimed or recycled concrete equivalent.

SITE GRADING NOTES:

EARTHWORK COMPUTATION ESTIMATE: APPROXIMATELY 394 CY OF MATERIAL TO BE REMOVED FROM THE SITE.

SCALE: 1" = 20'-0"

10' 0' 20' 40'

TYPICAL SILT FENCE DETAIL

N.T.S.

REVISION & DATE

FERRY LANDING AT BEACON, LTD

DEVELOPERS · DESIGNERS · BUILDERS

POST OFFICE BOX 294

BEACON, NY 12508

SITE GRADING PLAN

FOR

FERRY LANDING AT BEACON

BEEKMAN AND FERRY STREET

BEACON, NY 12508

DATED: FEBRUARY 21, 2019

SCALE: 1" = 20'-0"

DRAWING:

4 OF 9