


CURB ABUTTING SIDEWALK


STEEL CURB NOTE:
STEEL CURB TO BE GRADE A588 STEEL



CURB ABUTTING LANDSCAPING


STEEL CURB DETAIL

NOT TO SCALE



CURB ABUTTING SIDEWALK


CONCRETE CURB NOTE:
CONCRETE CURB TO BE 4,000 PSI CAST IN PLACE CONCRETE




CURB ABUTTING LANDSCAPING

CAST IN PLACE CONCRETE CURB DETAIL

NOT TO SCALE



TYPICAL CONCRETE SIDEWALK PLAN



TYPICAL CONCRETE SIDEWALK SECTION

CONCRETE SIDEWALK NOTES:

1. ALL CONCRETE SIDEWALKS TO BE 3,500 PSI CAST IN PLACE CONCRETE.
2. PROVIDE HAND TOOLED TRANSIVERSE CONTROL JOINTS @ 5'-0" O.C. MAX.
3. PROVIDE PRE MOLDED EXPANSION JOINTS WITH HAND TOOLED EDGES @ 20'-0" O.C. MAX.
4. REINFORCING FOR CONCRETE TO BE 6 x 6 - W1.4 x 1.4 WWM INSTALLED AT SLAB MID DEPTH
5. ALL EXPOSED CONCRETE SURFACE TO HAVE BROOM TEXTURE FINISH.
6. JOINTS WILL NOT BE SAWCUT.
7. ALL EXPOSED CONCRETE SURFACE TO BE TREATED WITH SUREBOND (OR EQUAL) SIDEWALK SEALER IN ACCORDANCE WITH MANUFACTURE'S INSTRUCTIONS.

TYPICAL CONCRETE SIDEWALK DETAIL

NOT TO SCALE

REVISION & DATE

FERRY LANDING AT BEACON, LTD

DEVELOPERS · DESIGNERS · BUILDERS

POST OFFICE BOX 294

BEACON, NY 12508

SITE DETAILS PLAN

FOR

FERRY LANDING AT BEACON

BEEKMAN AND FERRY STREET

BEACON, NY 12508

DATED: OCTOBER 13, 2017

SCALE: NONE

DRAWING:

9 OF 9