

INSPECTION SCHEDULE & LONG TERM MAINTENANCE OF STORMWATER STRUCTURES

CATCH BASINS AND PIPING:

ALL CATCH BASINS SHALL BE INSPECTED AFTER EACH STORM EVENT FOR SEDIMENT ACCUMULATION, AND DEBRIS, AND REMOVE AS NECESSARY. WHEN SEDIMENT ACCUMULATION WITHIN THE CATCH BASIN SUMP REACHES 1/2 OF THE SUMP DEPTH, IT SHALL BE REMOVED. ASSOCIATED PIPING SHALL BE INSPECTED ANNUALLY AND ACCUMULATED SEDIMENT SHALL BE REMOVED AS NEEDED. HYDRODYNAMIC DEVICE:

THE VORTEX UNITS SHALL BE INSPECTED QUARTERLY DURING THE FIRST YEAR OF OPERATION. THE MANUFACTURER RECOMMENDS THAT THE CDS UNITS BE INSPECTED BI-ANNUALLY (ONCE IN THE SPRING AND ONCE IN THE FALL). THE STRUCTURE SHALL BE VISUALLY INSPECTED FOR BLOCKAGES OR OBSTRUCTIONS IN THE INLET OR SEPARATION SCREEN. THE INSPECTION SHOULD ALSO QUANTIFY ACCUMULATION OF HYDROCARBONS, SEDIMENT AND TRASH WITHIN THE SYSTEM. INSPECTIONS AND MAINTENANCE SHALL BE PERFORMED BY QUALIFIED PERSONNEL WITH ADEQUATE TRAINING IN THESE TYPES OF UNITS. THE UNITS SHALL BE CLEANED BY VACUUM TRUCK ONCE A YEAR (EXCEPT FOR THE FIRST YEAR WHERE MORE FREQUENT CLEANINGS MAY BE REQUIRED).

UNDERGROUND DETENTION/INFILTRATION: THE UNDERGROUND DETENTION/INFILTRATION AREA SHALL BE INSPECTED MONTHLY FOR SEDIMENT AND DEBRIS ACCUMULATION. INFLOW PIPES. OUTLET STRUCTURES AND SPILLWAYS SHOULD ALSO BE INSPECTED FOR SEDIMENT AND DEBRIS MONTHLY. ANY ACCUMULATED SEDIMENT OR DEBRIS SHOULD BE REMOVED AS NECESSARY BY MEANS OF A VACUUM TRUCK. AFTER STORM EVENTS, THE UNDERGROUND DETENTION/INFILTRATION AREA'S DE-WATERING DURATION SHOULD ALSO BE MONITORED. IF IT TAKES LONGER THAN 24 HOURS TO DE-WATER, THE BASIN SHALL BE JET CLEANED TO PROVIDE FULL DE-WATERING IN 24 HOURS. SEDIMENT SHALL BE

CLEANED OUT OF THE INFILTRATION BASIN ANNUALLY. **EXISTING UNDERGROUND UTILITY NOTES:** 1. CONTRACTOR SHALL DIG TEST PITS TO VERIFY LOCATION, SIZE AND PIPE MATERIAL OF EXISTING UNDERGROUND UTILITIES. IF ANY

EXISTING UTILITIES ARE NOT IN THE LOCATION WHERE THEY ARE SHOWN ON THE PLAN, IT SHALL BE BROUGHT TO THE ENGINEER'S

ATTENTION IMMEDIATELY. **GENERAL CONSTRUCTION NOTES:** 

1. ALL OTHER UTILITIES (TELEPHONE, ELECTRIC, GAS, CABLE, ETC.) SHALL BE INCORPORATED PRIOR TO CONSTRUCTION. ALL SUCH UTILITY DESIGNS SHALL BE DEVELOPED IN COOPERATION WITH THE RESPECTIVE UTILITY COMPANIES.


2. THE CONTRACTOR SHALL PERFORM A UTILITIES CALL-OUT PRIOR TO CONSTRUCTION TO VERIFY ALL UNDERGROUND UTILITY LOCATIONS BY CONTACTING UFPO @ 1-800-962-7962. 3. THE CONTRACTOR SHALL FIELD VERIFY THE LOCATIONS AND INVERTS OF ALL CATCH BASINS & STORM SEWER LINES, SANITARY MANHOLES & SEWER LINES, WATERLINES AND OTHER UNDERGROUND UTILITY LINES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL NOT ASSUME THAT ALL LOCATIONS AS SHOWN ON THE PLAN ARE CORRECT. INVESTIGATIVE TEST PITS MAY BE REQUIRED TO VERIFY

4. PIPE CONNECTIONS TO ALL CATCH BASINS SHALL BE MADE WATERTIGHT, WITH PARTICULAR ATTENTION BEING PAID TO CONNECTIONS LOCATED WITHIN 10 FEET OF SEWER MAINS (AND SERVICE LATERALS).

AND AN OPERATION AND MAINTENANCE PLAN MANUAL SHALL BE PROVIDED TO THE CITY OF BEACON.

**POST CONSTRUCTION NOTES:** 

UPON COMPLETION OF CONSTRUCTION OF THE STORMWATER FACILITIES, AS-BUILT DRAWINGS OF ALL STORMWATER PRACTICES



STC	ORM SEWER STRUCTURE TABLE
STRUCTURE	STRUCTURE DETAILS
EX CB1	RIM = 103.16 SUMP = 98.92 EX CB1-YD7 INV OUT = 98.90
EX CB3	RIM = 81.86 SUMP = 76.94 STMH3-EX CB3 INV IN = 67.80 EX CB3 OUT INV OUT = 67.09
STMH1	RIM = 121.00 SUMP = 110.60 INF A OUT-STMH1 INV IN = 111.90 STMH1-STMH2 INV OUT = 111.60
STMH2	RIM = 100.07 SUMP = 88.60 YD8-STMH2 INV IN = 89.60 STMH1-STMH2 INV IN = 89.70 STMH2-EX CB2 INV OUT = 89.60
STMH3	RIM = $84.89$ SUMP = $77.50$ INF B(1)-STMH3 INV IN = $79.50$ INF B(2)-STMH3 INV IN = $80.30$ STMH3-EX CB3 INV OUT = $73.30$
WQI1	RIM = 120.50 SUMP = 111.80 CB7-WQI1 INV IN = 117.60 CB8-WQI1 INV IN = 112.90 WQI1-CULTEC INV OUT = 112.80
YD1	RIM = 139.00 SUMP = 133.80 YD1-YD2 INV OUT = 136.00

STORM	SEWER STRUCTURE TABLE
STRUCTURE	STRUCTURE DETAILS
YD2	RIM = 135.90 SUMP = 131.90 YD1-YD2 INV IN = 133.00 YD2-YD3 INV OUT = 132.90
YD3	RIM = 131.76 SUMP = 127.70 YD2-YD3 INV IN = 128.80 YD3-CB2 INV OUT = 128.70
YD4	RIM = 129.00 SUMP = 125.10 YD4-CB4 INV OUT = 126.10
YD5	RIM = 117.20 SUMP = 113.30 YD5-YD6 INV OUT = 114.30
YD7	RIM = 94.50 SUMP = 90.50 EX CB1-YD7 INV IN = 91.60 YD7-YD8 INV OUT = 91.50
YD8	RIM = 92.20 SUMP = 85.34 YD7-YD8 INV IN = 89.80 YD8-STMH2 INV OUT = 89.80

STORM SEWER PIPE TABLE					
PIPE NAME	LENGTH	SIZE AND MATERIAL	SLOPE		
CB1-CB2	35 LF	15" ø CORR HDPE	1.15%		
CB2-CB3	24 LF	15" ø CORR HDPE	1.26%		
CB3-CB5	63 LF	15" ø CORR HDPE	0.95%		
CB4-CB5	44 LF	15" ø CORR HDPE	1.14%		
CB5-CB6	84 LF	15" ø CORR HDPE	2.15%		
CB6-CB7	93 LF	15" ø CORR HDPE	2.59%		
CB7-WQI1	8 LF	15" ø CORR HDPE	5.07%		
CB8-WQI1	56 LF	15" ø CORR HDPE	1.07%		
ES1-ES2	25 LF	15" ø CORR HDPE	1.22%		

	STORM SEWER PIPE TABLE				
1:1	PIPE NAME	LENGTH	SIZE AND MATERIAL	SLOF	
• •	EX CB1-YD7	128 LF	15" Ø CORR HDPE	5.70	
,	INF A OUT-STMH1	8 LF	12" ø CORR HDPE	1.32	
, , 	INF B(1)-STMH3	32 LF	4" Ø CORR HDPE	4.69	
;	INF B(2)-STMH3	32 LF	6" Ø CORR HDPE	4.69	
,	STMH1-STMH2	124 LF	15" Ø CORR HDPE	17.72	
,	STMH2-EX CB2	87 LF	15" ø CORR HDPE	1.04	
<u>,</u>	STMH3-EX CB3	37 LF	15" Ø CORR HDPE	14.91	
<u>;</u>	WQI1-CULTEC	11 LF	15" Ø CORR HDPE	16.52	
,	YD1-YD2	82 LF	15" Ø CORR HDPE	3.64	


STORM SEWER PIPE TABLE			
PIPE NAME	LENGTH	SIZE AND MATERIAL	SLOP
YD2-YD3	66 LF	15" ø CORR HDPE	6.24
YD3-CB2	81 LF	15" ø CORR HDPE	8.68
YD4-CB4	101 LF	15" ø CORR HDPE	2.96
YD5-YD6	29 LF	15" ø CORR HDPE	1.049
YD6-CB8	24 LF	15" ø CORR HDPE	1.24%
YD7-YD8	64 LF	15" ø CORR HDPE	2.649
YD8-STMH2	38 LF	15" ø CORR HDPE	0.53

APPROVED BY RESOLUTION OF THE PLANNING BOARD OF THE CITY OF BEACON, NEW YORK, ON THE

	SANITARY SEWER STRUCTURE TABLE		
[	STRUCTURE	STRUCTURE DETAILS	
	EX SMH	RIM = 89.97 SMH5 TO EX SMH INV IN = 83.75	
	SMH1	RIM = 126.90 SMH1-SMH2 INV OUT = 120.80	
	SMH2	RIM = 130.17 SMH2-SMH3 INV OUT = 124.00	
	SMH3	RIM = 128.54 SMH1-SMH2 INV IN = 120.30 SMH2-SMH3 INV IN = 120.30 SMH3-SMH4 INV OUT = 120.20	
	SMH4	RIM = 117.59 SMH3-SMH4 INV IN = 112.80 SMH4-SMH5 INV OUT = 95.27	
	SMH5	RIM = 92.53 SMH4-SMH5 INV IN = 85.00 SMH5 TO EX SMH INV OUT = 84.96	

3111	110 10 27		1.00
SANITARY SEWER PIPE TABLE			
PIPE NAME	LENGTH	SIZE AND MATERIAL	SLOPE
SMH1-SMH2	84 LF	8" SDR-35 PVC	0.59%
SMH2-SMH3	49 LF	8" SDR-35 PVC	7.51%
SMH3-SMH4	287 LF	8" SDR-35 PVC	2.58%
SMH4-SMH5	51 LF	8" SDR-26 PVC	20.00%
SMH5 TO EX SMH	81 LF	8" SDR-35 PVC	1.42%

	DAY C CONDITIONS OF SAID RESC AS APPROVED, SHALL VOI	DLUTION. ANY CHANGE, ERASURE	, SUBJECT TO ALL REQUIREMENTS A E, MODIFICATION OR REVISION OF THIS P	ND LAT,
	SIGNED THIS	DAY OF	, 20, BY	
75		CHAIRMAN		
)		SECRETARY		
0	IN ABSENCE OF THE CHAIL RESPECTIVELY MAY SIGN I		ING CHAIRMAN OR ACTING SECRETARY	
)				



NYS LICENSE NO. 082716

REVI	SIONS:		
NO.	DATE	DESCRIPTION	BY
1	8/29/2017	PER PLANNING BOARD COMMENTS	DGK
2	9/26/2017	PER PLANNING BOARD COMMENTS	DGK
3	10/31/2017	REVISED RETAINING WALL	DGK

**Grading and Utility Plan** Sheet 7 of 11

**EXISTING FIRE**