

INSPECTION SCHEDULE & LONG TERM MAINTENANCE OF STORMWATER STRUCTURES

CATCH BASINS AND PIPING:

ALL CATCH BASINS SHALL BE INSPECTED AFTER EACH STORM EVENT FOR SEDIMENT ACCUMULATION, AND DEBRIS, AND REMOVE AS NECESSARY. WHEN SEDIMENT ACCUMULATION WITHIN THE CATCH BASIN SUMP REACHES 1/2 OF THE SUMP DEPTH, IT SHALL BE REMOVED. ASSOCIATED PIPING SHALL BE INSPECTED ANNUALLY AND ACCUMULATED SEDIMENT SHALL BE REMOVED AS NEEDED. HYDRODYNAMIC DEVICE:

THE CDS STORMWATER TREATMENT SYSTEM IS A HIGH-PERFORMANCE HYDRODYNAMIC SEPARATOR AND REQUIRES REGULAR INSPECTION AND MAINTENANCE TO ENSURE OPTIMAL PERFORMANCE. MAINTENANCE FREQUENCY WILL BE DRIVEN BY SITE CONDITIONS. THE MANUFACTURER SUGGESTS QUARTERLY VISUAL INSPECTIONS TO DETERMINE THE ACCUMULATION OF POLLUTANTS, AND SUGGESTS ANNUAL REMOVAL OF ACCUMULATED POLLUTANTS. VORTEX UNITS SHALL BE INSPECTED QUARTERLY, GENERALLY AROUND THE CHANGE OF EACH SEASON. INSPECTIONS AND MAINTENANCE SHALL BE PERFORMED BY QUALIFIED PERSONNEL WITH ADEQUATE TRAINING IN THESE TYPES OF UNITS. THE UNITS SHALL BE CLEANED BY VACUUM TRUCK. ADDITIONAL CLEANINGS SHOULD BE ANTICIPATED DURING THE FIRST YEAR OF OPERATION. THE RECOMMENDED CLEANOUT OF SOLIDS WITHIN THE CDS UNIT'S SUMP SHOULD OCCUR AT 75% OF

UNDERGROUND DETENTION/INFILTRATION:

BEST MANAGEMENT PRACTICE FOR MAINTAINING OPTIMUM PERFORMANCE OF THE UNDERGROUND INFILTRATION SYSTEM IS A COMBINATION OF THE FOLLOWING:

1. PROPER MAINTENANCE OF THE PRETREATMENT HYDRODYNAMIC DEVICE,

REMOVAL OF ACCUMULATED SEDIMENT FROM THE UPSTREAM CATCH BASIN AND STORMWATER COLLECTION SYSTEM, AND BY MAINTAINING THE SITE IMPERVIOUS AND LAWN AREAS IN A STABLE CONDITION. ANY FUTURE LAND DISTURBANCE ASSOCIATED WITH MAINTENANCE OF THE BUILDINGS AND GROUNDS SHALL CAREFULLY PREPARE AN EROSION AND SEDIMENT CONTROL PLAN TO LIMIT TRANSPORT OF SEDIMENT LADEN RUNOFF TO THE COLLECTION SYSTEM. THE CULTEC SYSTEM SHALL BE EQUIPPED WITH AN INSPECTION PORT LOCATED ON THE INLET ROW. THE INSPECTION PORT IS A CIRCULAR CAST BOX PLACED IN A RECTANGULAR CONCRETE COLLAR. WHEN THE LID IS REMOVED, A 6-INCH PIPE WITH A SCREW-IN PLUG WILL BE EXPOSED. REMOVE THE PLUG. THIS WILL PROVIDE ACCESS TO THE CULTEC CHAMBER ROW BELOW. FROM THE SURFACE, THROUGH THIS ACCESS, THE SEDIMENT MAY BE MEASURED AT THIS LOCATION. A STADIA ROD MAY BE USED TO MEASURE THE DEPTH OF SEDIMENT IF ANY IN THIS ROW. ADDITIONALLY, CCTV INSPECTION OF THIS ROW CAN BE DEPLOYED THROUGH THIS ACCESS PORT TO DETERMINE IF ANY SEDIMENT HAS ACCUMULATED. IF THE DEPTH OF SEDIMENT IS IN EXCESS OF 3 INCHES, THEN THIS ROW SHOULD BE CLEANED WITH HIGH PRESSURE WATER THROUGH A CULVERT CLEANING NOZZLE. THIS WOULD BE CARRIED OUT THROUGH THE UPSTREAM PRETREATMENT DEVICE. THE ACCESS POINT THROUGH THE HYDRODYNAMIC DEVICE REQUIRES A TECHNICIAN TRAINED IN CONFINED SPACE ENTRY WITH PROPER GAS DETECTION EQUIPMENT. THIS INDIVIDUAL MUST BE EQUIPPED WITH THE PROPER SAFETY EQUIPMENT FOR ENTRY INTO THE HYDRODYNAMIC DEVICE. THE INLET ROW IS PLACED ON A POLYETHYLENE LINER TO PREVENT SCOURING OF THE WASHED STONE BENEATH THIS ROW. THIS FACILITATES THE FLUSHING OF THIS ROW WITH HIGH PRESSURE WATER THROUGH A CULVERT CLEANING NOZZLE. THE NOZZLE IS DEPLOYED THROUGH THE HYDRODYNAMIC DEVICE AND EXTENDED TO THE END OF THE ROW. THE WATER IS TURNED ON AND THE INLET ROW IS BACK-FLUSHED INTO THE HYDRODYNAMIC DEVICE WHERE IT IS REMOVED BY USING A VACUUM TRUCK. MAINTENANCE GUIDELINES:

1. THE OWNER SHALL KEEP A MAINTENANCE LOG WHICH SHALL INCLUDE DETAILS OF ANY EVENTS WHICH WOULD HAVE AN EFFECT ON THE SYSTEM'S OPERATIONAL CAPACITY. THE OPERATION AND MAINTENANCE PROCEDURE SHALL BE REVIEWED PERIODICALLY AND CHANGED TO MEET SITE CONDITIONS. MAINTENANCE OF THE STORMWATER MANAGEMENT SYSTEM SHALL BE PERFORMED BY QUALIFIED WORKERS AND SHALL FOLLOW APPLICABLE OCCUPATIONAL HEALTH AND SAFETY REQUIREMENTS.

4. DEBRIS REMOVED FROM THE STORMWATER MANAGEMENT SYSTEM SHALL BE DISPOSED OF IN ACCORDANCE WITH APPLICABLE LAWS AND REGULATIONS. SUGGESTED MAINTENANCE SCHEDULE (TO BE RE-ASSESSED BY THE OPERATOR PERIODICALLY BASED ON SITE CONDITIONS AND

EVALUATION OF SYSTEM FUNCTIONALITY): 1. YEAR 1: INSPECT INLETS AND OUTLETS MONTHLY FOR ANY CLOGGING, AND REMOVE DEBRIS AS MAY BE NECESSARY. INSPECT THE SURFACE AROUND THE CHAMBERS FOR ANY DEPRESSIONS. 2. YEAR 2 AND AFTER: INSPECT INLETS AND OUTLETS EVERY SPRING AND FALL FOR ANY CLOGGING, AND REMOVE DEBRIS AS MAY BE NECESSARY. INSPECT THE SURFACE AROUND THE CHAMBERS FOR ANY DEPRESSIONS.

3. 2 YEARS AFTER COMMISSIONING: INSPECT THE INTERIOR OF THE STORMWATER MANAGEMENT CHAMBERS THROUGH INSPECTION PORT FOR DEFICIENCIES USING CCTV OR COMPARABLE TECHNIQUE.

4. 9 YEARS AFTER COMMISSIONING, AND EVERY 9 YEARS THEREAFTER (OR AS MAY BE NEEDED): CLEAN STORMWATER MANAGEMENT CHAMBERS AND FEED CONNECTORS OF ANY DEBRIS. INSPECT THE INTERIOR OF THE STORMWATER MANAGEMENT CHAMBERS THROUGH INSPECTION PORT FOR DEFICIENCIES USING CCTV OR COMPARABLE TECHNIQUE. 5. 45 YEARS AFTER COMMISSIONING: A PROFESSIONAL ENGINEER SHALL ASSESS THE REMAINING LIFE EXPECTANCY OF THE STORMWATER MANAGEMENT CHAMBERS AND RECOMMEND ACTIONS TO REHABILITATE, RESTORE OR REPLACE THE STORMWATER

MANAGEMENT CHAMBERS AS MAY BE REQUIRED. 6. ANNUALLY: CONFIRM THAT NO UNAUTHORIZED MODIFICATIONS HAVE BEEN PERFORMED TO THE SITE THAT MAY IMPACT THE ADEQUATE FUNCTIONING OF THE SYSTEM. 7. PERIODICALLY: MONITOR WATER LEVELS IN THE CHAMBER SYSTEM FOLLOWING SIGNIFICANT STORM EVENTS. DEWATERING OF THE

SYSTEM SHOULD TAKE NO LONGER THAN 24 HOURS. **EXISTING UNDERGROUND UTILITY NOTES:**

1. CONTRACTOR SHALL DIG TEST PITS TO VERIFY LOCATION, SIZE AND PIPE MATERIAL OF EXISTING UNDERGROUND UTILITIES. IF ANY EXISTING UTILITIES ARE NOT IN THE LOCATION WHERE THEY ARE SHOWN ON THE PLAN, IT SHALL BE BROUGHT TO THE ENGINEER'S

ATTENTION IMMEDIATELY. **GENERAL CONSTRUCTION NOTES:**

 ALL OTHER UTILITIES (TELEPHONE, ELECTRIC, GAS, CABLE, ETC.) SHALL BE INCORPORATED PRIOR TO CONSTRUCTION. ALL SUCH UTILITY DESIGNS SHALL BE DEVELOPED IN COOPERATION WITH THE RESPECTIVE UTILITY COMPANIES. 1. THE CONTRACTOR SHALL PERFORM A UTILITIES CALL-OUT PRIOR TO CONSTRUCTION TO VERIFY ALL UNDERGROUND UTILITY

LOCATIONS BY CONTACTING UFPO @ 1-800-962-7962. 2. THE CONTRACTOR SHALL FIELD VERIFY THE LOCATIONS AND INVERTS OF ALL CATCH BASINS & STORM SEWER LINES, SANITARY MANHOLES & SEWER LINES. WATERLINES AND OTHER UNDERGROUND UTILITY LINES PRIOR TO CONSTRUCTION. THE CONTRACTO SHALL NOT ASSUME THAT ALL LOCATIONS AS SHOWN ON THE PLAN ARE CORRECT. INVESTIGATIVE TEST PITS MAY BE REQUIRED

3. PIPE CONNECTIONS TO ALL CATCH BASINS SHALL BE MADE WATERTIGHT, WITH PARTICULAR ATTENTION BEING PAID TO CONNECTIONS LOCATED WITHIN 10 FEET OF SEWER MAINS (AND SERVICE LATERALS).

POST CONSTRUCTION NOTES: 1. RECORD DRAWINGS OF THE PROJECT INCLUDING ALL UTILITIES WILL BE PROVIDED TO THE BUILDING INSPECTOR AFTER

2. AN OPERATION AND MAINTENANCE PLAN MANUAL SHALL BE PROVIDED TO THE CITY OF BEACON BUILDING INSPECTOR FOLLOWING

COMPLETION OF THE STORMWATER FACILITIES.

RETAINING WALL NOTES:

1. CONTRACTOR TO REFER TO PLANS AND SPECIFICATIONS FOR THE RETAINING WALL AS PREPARED BY CIVIL DESIGN PROFESSIONALS. 2. CLAY KEY AND/OR STONE CHIMNEY DRAIN TO BE INSTALLED AT THE DIRECTION OF THE FINAL DESIGN AS APPROVED BY THE CITY


3. RETAINING WALL UNDERDRAINS TO BE INSTALLED AND DIRECTED TO THE CATCH BASINS ON THE DOWNHILL SIDE OF THE WALL AS SHOWN ON THE UTILITY PLAN.

<u>INFILTRATION TEST TABLE:</u>								
INFILTRATION TESTS RESULTS ESTABLISHED ON 9/17/2017 ALL TESTS PRESOAKED 24 HOURS PRIOR								
TEST ID	TEST HOLE BOTTOM ELEVATION	RESULTS						
IT1	110	>5" PER HOUR; >5" PER HOUR; >5" PER HOUR						
IT2	108	>5" PER HOUR; >5" PER HOUR; >5" PER HOUR						
IT3	108.5	>5" PER HOUR; >5" PER HOUR; >5" PER HOUR						
IT4	107.5	>5" PER HOUR; >5" PER HOUR; >5" PER HOUR						
IT5	108	>5" PER HOUR; >5" PER HOUR; >5" PER HOUR						
IT6	85	5/8" PER HOUR; 1/8" PER HOUR						
IT7	85	1-7/8" PER HOUR; 1-1/2" PER HOUR; 1-1/2" PER HOUR						

		DEEP TEST HOLE TABLE:
		DEEP TEST HOLE RESULTS ESTABLISHED ON 9/11/2017
TEST PIT ID	EX. ELEVATION	DESCRIPTION
TP1	125	0'-8' NON-NATIVE SILTY LOAM FILL WITH BRICKS, CONCRETE AND BOULDERS; 8'-15' BROWN SILTY-CLAY LOAM WITH COBBLES; NO GROUNDWATER, NO MOTTLING, NO BEDROCK
TP2	123.5	0'-8' NON-NATIVE SILTY LOAM FILL WITH BRICKS, CONCRETE AND BOULDERS; 8'-16.5' BROWN SILTY-CLAY LOAM WITH COBBLES; NO GROUNDWATER, MOTTLING AT 15', NO BEDROCK
TP3	122.5	0'-9' NON-NATIVE SILTY LOAM FILL WITH BRICKS, CONCRETE AND BOULDERS; 8'-15' BROWN SILTY-CLAY LOAM WITH COBBLES; NO GROUNDWATER, NO MOTTLING, NO BEDROCK
TP4	124	0'-8' NON-NATIVE SILTY LOAM FILL WITH BRICKS, CONCRETE AND BOULDERS; 8'-17.5' BROWN SILTY-CLAY LOAM WITH COBBLES; NO GROUNDWATER, NO MOTTLING, NO BEDROCK
TP5	124	0'-8' NON-NATIVE SILTY LOAM FILL WITH BRICKS, CONCRETE AND BOULDERS; 8'-15' BROWN SILTY-CLAY LOAM WITH COBBLES; NO GROUNDWATER, NO MOTTLING, NO BEDROCK
TP6	90	0'-1' TOPSOIL; 1'-6' BROWN SILTY LOAM WITH GRAVEL; NO GROUNDWATER, NO MOTTLING, BEDROCK @ 6'
TP7	91	0'-1' TOPSOIL; 1'-4' BROWN SILTY LOAM WITH GRAVEL; NO GROUNDWATER, NO MOTTLING, BEDROCK @ 4'

APPROVED BY RESOLUTION OF THE PLANNING BOARD OF THE CITY OF BEACON, NEW YORK, ON THE

N ABSENCE OF THE CHAIRMAN OR SECRETARY, THE ACTING CHAIRMAN OR ACTING SECRETARY



NYS LICENSE NO. 082716

			_
REVI	SIONS:		
NO.	DATE	DESCRIPTION	
1	8/29/2017	PER PLANNING BOARD COMMENTS	
2	9/26/2017	PER PLANNING BOARD COMMENTS	
3	10/31/2017	REVISED RETAINING WALL	
4	11/28/2017	REVISED STAIRWAY TO FERRY STREET	
5	12/22/2017	REMOVED INTERNAL PATH AND POCKET PARK	
6	01/30/2018	PER PLANNING BOARD COMMENTS	
7	02/27/2018	PER PLANNING BOARD COMMENTS	

Grading Plan

Sheet 7 of 15

Scale: As Noted

July 25, 2017

Beacon, New York 12508