

<u>LEGEND</u>

(A) 1.5" ASPHALT CONCRETE TOP COURSE- NYSDOT TYPE F1

(B) 3.0" ASPHALT CONCRETE BINDER COURSE— NYSDOT TYPE F9
(C) 3.0" ASPHALT BASE COURSE— NYSDOT TYPE F9


## NOTES:

1. SAW CUT MIN. 18" BEYOND EXCAVATION WITH SMOOTH EDGES. 18" JOINT BETWEEN EXISTING AND NEW TOP COURSE TO BE MILLED. JOINT TO BE SEALED WITH POLYMER MODIFIED SEALER.

2. FURNISH, PLACE, AND COMPACT SUBBASE.
3. TACK COAT IN ACCORDANCE WITH NYSDOT STANDARD SPEC.
4. FURNISH AND PLACE ASPHALT CONCRETE PAVEMENT AS SPECIFIED.

PAVEMENT RESTORATION DETAIL

NOT TO SCALE




## NOTES:

CONCRETE CURB SHALL BE 4,000 PSI CAST—IN—PLACE, AND IN ACCORDANCE WITH NYSDOT STANDARD SPECIFICATION SECTION 609.
 EXPANSION JOINTS OF 1/2" CELLULOSE OR SIMILAR MATERIAL SHALL BE PLACED AT 10 FOOT INTERVALS.
 FOR MOUNTABLE CURBS ABUTTING SIDEWALK OR OTHER HARDSCAPE, REFER TO "ABUTTING SIDEWALK" DETAIL.


CAST-IN-PLACE CONCRETE CURB DETAIL
NOT TO SCALE

4. CONCRETE SHALL BE SEALED WITH A SALT RESISTANT SEALER.



OWNER'S CONSENT:
THE UNDERSIGNED OWNER OF THE PROPERTY HEREON STATES THAT HE IS FAMILIAR WITH THIS MAP, ITS CONTENTS AND ITS LEGENDS AND HEREBY CONSENTS TO ALL SAID TERMS AND CONDITIONS AS STATED HEREON.

GARY JOSEPH OR TIM OWEN DATE



1. 10' SPACING OF CONTROL JOINTS SHALL BE USED FOR CAST IN PLACE CONCRETE CURBS.
2. MATERIAL AND METHODS OF CONSTRUCTION SHALL BE IN CONFORMANCE WITH THE NEW YORK STATE DEPARTMENT OF TRANSPORTATION (NYSDOT) STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS, DATED JANUARY 2, 2002, AND ALL ADDENDA THERETO; THE ONLY EXCEPTION BEING THAT THE WORK OF THIS CONTRACT SHALL BE

MEASURED IN ENGLISH UNITS.
3. ALL CONCRETE SHALL BE 3,500 PSI CLASS A CONCRETE. CONCRETE MATERIALS, PLACEMENT, AND CONSTRUCTION SHALL CONFORM WITH SECTION 500 OF THE ABOVE REFERENCED NYSDOT STANDARD SPECIFICATIONS.

4. REINFORCING STEEL FOR CONCRETE SHALL CONFORM WITH SECTION 556 — REINFORCING STEEL FOR CONCRETE STRUCTURES OF THE ABOVE REFERENCED NYSDOT STANDARD SPECIFICATIONS AND AS SPECIFICALLY CALLED OUT IN THE DRAWINGS.

5. ALL EXPOSED SURFACED SHALL HAVE A BROOM TEXTURED FINISH.

6. EXPANSION JOINTS SHALL BE LOCATED A MAXIMUM OF 20' ON CENTER, OR AS INDICATED ON PLANS.

7. JOINTS SHALL NOT BE SAW CUT.
8. EXPOSED CONCRETE SURFACES SHALL BE TREATED WITH "SUREBOND"/"SAFEBOND" SB-7000 INTENSIFIER BRIGHT PROTECTOR AND SIDEWALK SEALER, OR EQUAL. RATE AND METHOD OF APPLICATION SHALL BE IN ACCORDANCE WITH MANUFACTURE'S RECOMMENDATIONS.

9. SUBBASE MATERIAL SHALL CONFORM WITH SECTION 304 OF THE ABOVE REFERENCED NYSDOT STANDARD.


10. WHERE IT IS NECESSARY TO PLACE FILL FOR PURPOSE OF BRINGING THE SUBGRADE ELEVATION UP TO A SPECIFIED GRADE, THE FILL MATERIAL PLACED SHALL BE IN CONFORMATION WITH SECTION 203—EXCAVATION AND EMBANKMENT OF THE ABOVE REFERENCED NYSDOT STANDARD SPECIFICATIONS.


NOT TO SCALE

11. ALL WORK SHALL CONFORM WITH SECTION 608-SIDEWALK, DRIVEWAYS, AND BICYCLE PATHS OF THE ABOVE REFERENCED NYSDOT STANDARD SPECIFICATIONS.

12. CONCRETE SHALL BE SEALED WITH A SALT RESISTANT SEALER.

CONCRETE SIDEWALK DETAIL






NOTE:

1. RESEED AND STABILIZE GRASS AREAS AFTER ASPHALT INSTALLATION.

LOT 2 DRIVEWAY ENTRANCE DETAIL

NOT TO SCALE



APPROVED BY RESOLUTION OF THE PLANNING BOARD OF THE CITY OF BEACON, NEW YORK, ON THE

\_\_\_\_\_\_\_DAY OF \_\_\_\_\_\_, 20\_\_\_\_\_, SUBJECT TO ALL REQUIREMENTS AND CONDITIONS OF SAID RESOLUTION. ANY CHANGE, ERASURE, MODIFICATION OR REVISION OF THIS PLAT, AS APPROVED, SHALL VOID THIS APPROVAL.

SIGNED THIS \_\_\_\_\_\_\_ DAY OF \_\_\_\_\_\_, 20\_\_\_\_\_, BY

\_\_\_\_\_\_ CHAIRMAN

\_\_\_\_\_\_ SECRETARY

IN ABSENCE OF THE CHAIRMAN OR SECRETARY, THE ACTING CHAIRMAN OR ACTING SECRETARY

SITE DETAILS

## 38 ST. LUKES SUBDIVISION

38 ST. LUKES PLACE
CITY OF BEACON
DUTCHESS COUNTY, NEW YORK
TAX ID: 6054-38-156634
SCALE: NTS
APRIL 24, 2018



DRAW	N BY: AG	CHECKED BY: DGK JOB NO.: 2018	3:012
REVISIONS:			
NO.	DATE	DESCRIPTION	BY
1	05/29/18	REVISED PER CONSULTANT COMMENTS	AG
2	06/26/18	ADDED SHEET	AG



RESPECTIVELY MAY SIGN IN THIS PLACE.

HUDSON LAND DESIGN
PROFESSIONAL ENGINEERING P.C.

174 MAIN STREET
BEACON, NEW YORK 12508
PH: 845-440-6926 F: 845-440-6637



JON D. BODENDORF, P.E. NYS LICENSE NO. 076245 DANIEL G. KOEHLER, P.E. NYS LICENSE NO. 082716

SHEET: 5 OF 5